


SINAP loop operations – summary of experience to data


Yuan FU

SINAP, CAS

2016.10


 钚基熔盐核能系统

 中国科学院上海应用物理研究所
Shanghai Institute of Applied Physics, Chinese Academy of Sciences



Outline


- 📖 General introduction
- 📖 Molten salt loop commissioning and operation
- 📖 TH experiments of molten salt loop and future planning



📖 General introduction

📖 Molten salt loop commissioning and operation


📖 TH experiments of molten salt loop and future planning



SINAP molten salt loop development

📖 From 2011, SINAP has developed 3 molten salt loops

- ❑ 1. HTS thermal test loop (HTS loop)
- ❑ 2. FLiNaK molten salt high temperature test loop (FLiNaK loop)
- ❑ 3. Nitrate natural circulation loop (NNCL)



HTS loop




Main design parameters:


Salt	$\text{KNO}_3\text{-NaNO}_2\text{-NaNO}_3(53\text{-}40\text{-}7\text{mol}\%)$
Design temperature	450°C
Work temperature	200-400°C
Flow rate	<2m/s
Design flux	2m ³ /h
Material of construction	Inconel600



Achievements:

- Validate system design and integration technologies of molten salt loop
- Carry out HT experiments via nitrate





FLiNaK Loop




Main design parameters:


Salt	LiF-NaF-KF (46.5-11.5-42mol%)
Design temperature	650°C
Work temperature	500-600°C
Design flux	15m ³ /h
Design pressure	<0.5MPa
Material of construction	Hastelloy-C276



Achievements:

- Validate system design and integration, loop layout and seal technologies of high temperature fluoride loop
- Develop principle prototypes of molten salt pump, valves, heat exchanger and high-temperature instrumentation, etc.





NNCL



Main design parameters:

Salt	$\text{KNO}_3\text{-NaNO}_2\text{-NaNO}_3(53\text{-}40\text{-}7\text{mol}\%)$
Design temperature	450°C
Work temperature	200-400°C
Material of construction	ss316



Achievements:


- Establish experimental platform to study molten salt natural circulation
- Gather experience on design and validation of passive decay heat removal system for the future fluoride-salt-cooled high temperature reactor





 General introduction

 Molten salt loop commissioning and operation

 TH experiments of molten salt loop and future planning



Main steps and contents of molten salt loop commissioning



Failures and solutions during loop commissioning



Storage tank

- ❑ Failure: crack happened between cylinder and head
- ❑ Reason: no heat-treatment after machining of vessel heads
- ❑ Solution: replace the old tank with a new one with heat-treated



Freeze valve

- ❑ Failure: valve body crack
- ❑ Reason: salt frozen at both ends of the valve body when valve opened
- ❑ Solution: install additional heaters on both ends of freeze valve to keep salt melted



Crucial commissioning and operation techniques for loop




Quality control of FLiNaK salt

- ❑ To control the content of water and oxygen under a low level (about 100ppm) by vacuum pumping and argon charging.
- ❑ Sampling and analysis of molten salt indicate that loop corrosion control keeps in a well condition and salt's quality is not going worse any more after loop operation.




Anti-freezing technology of loop system

- ❑ Heaters are installed outside all equipment and piping of the loop, which can preheat the loop system and add heat during operation.



Overall operation conditions of molten salt loop

- 📖 HTS Loop: 15,000 hours of accumulated running time; During the process heat transfer test section has been upgraded
- 📖 FLiNaK Loop: Thousands of hours of accumulated running time; During the process the high-power heater has been upgraded, now undergoes the installation of a prototype of SF0 heater
- 📖 NNCL: Thousands of hours of accumulated running time



Operation and Experiment contents



System Operation

- Isothermal Operation
 - Isothermal operation within various flux
- Temperature difference Operation
 - General adjustment via electrical heating and air cooling
 - Design verification of heat exchanger



Equipment performance test

- Molten salt pump performance experiment
- Freeze valve switching test
- Air cooling performance test of heat exchanger
- Functional validation of flexible supports for equipment



TH experiments


... ..

- Successful operation of principle prototype of pump, heat exchanger, freeze valve and instrumentation such as flow meter, pressure transmitter and level meter, and test data has been collected.
- Technical supports and data reference for R&D of engineering prototype and nuclear equipment.




Principle prototype of molten salt pump and salt-air heat exchanger


Testing results of molten salt loop equipments




(1) Validation of pump frequency and flow meter reading




(2) Temperature distribution of molten salt pump key parts



(3) Switching response of freeze valve



- 📖 General introduction
- 📖 Molten salt loop commissioning and operation
- 📖 TH experiments of molten salt loop and future planning



TH experiments completed in molten salt loop

HTS loop

- Circular tube HT tests
- Enhanced HT tube tests

FLiNaK loop


- Salt-air heat exchanger steady HT tests
- Molten salt pump hydraulic tests

NNCL


- Nitrate natural circulation
- Residual heat removal validation



HTS loop HT experiments



Schematic diagram of the test section and the oil loop in the HTS loop



Circular tube HT tests

Suggested new correlation


$$Nu = 0.0275 Re^{0.8026} Pr^{1/3} (\mu_b / \mu_w)^{0.14}$$

(20000 < Re < 50000, 11 < Pr < 27)

➤ Uncertainty of Nu: ± 7.8%

HT correlations comparison (deviation)



- Gnielinski (+7%)
- Sieder–Tate (-8%)
- Hausen (-10%)
- Dittus–Boelter (-20%)



Comparison of the suggested new correlation for turbulent flow with classical HT correlations


FLiNaK loop experiments



Salt-air heat exchanger steady HT tests

-  To obtain the heat transfer coefficients of the salt-air heat exchanger at different flow conditions
-  To validate the heat exchanger design (HT coefficient design value: $70\text{W}/\text{m}^2\text{K}$)


Molten salt pump hydraulic tests

-  To obtain the pump hydraulic characteristics at steady state









Molten salt pump hydraulic test result



NNCL experiments



-  **The experimental prove that:**
-  A stable natural circulation can be formed in a short time, and the heat can be removed continuously.
 -  The molten salt natural circulation loop is feasible for the residual heat removal of molten salt reactor.

Test plans for the loops




Heat transfer tests on the FLiNaK test loop

- Pebble-bed heat transfer tests
- Convective heat transfer tests in a circular pipe



Transient tests for system code validation purpose on the two loops

- System and key equipment heat loss calibration tests
- Power transients
- Salt flow rate transients
- Heat exchanger load transients



THANKS!

